

1 050499

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,401-0000
150' NE S/2 S/2 NE, SEC. 20, T 29 S, R 22 W/EX

3075 feet from S section line
1215 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Ellis Well # 1-P

Operator: Pickrell Drilling Company
Name & Address: 110 North Market, Suite 205
Wichita, KS 67202

County Ford 179.08

Well Total Depth 5510 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 602

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 10 Month: April Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427

ware: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1470' with 50 sx cement

2nd plug at 720' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 pm Day: 10 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 720' with 70
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 5-3-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 7938