

1 010130

15-097-20166-0001

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097=20,166A

C SW SE , SEC. 36 , T 29 S, R 20 W XX  
660 feet from S section line  
1980 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Ralstin Well # B1

Operator: J. Mark Richardson

County Kiowa 171.41

Name &amp; Address 640 Century Plaza Building

Well Total Depth 5274 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1127

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 pm Day: 2 Month: May Year: 19 86

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 5273' Perfs at 5129-35'; 5140-46' (squeezed); 5132-42'; 4797-4802'

1st plug sand back to 4740' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 100 sx cement.Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2:45 pm Day: 2 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4740' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel 50 sx cement, 10 sx  
gel, 1 sack hulls and 100 sx cement. Could not use plug container.

Maximum pressure 400 psi and shut in 300 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 4600' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)INVOICED  
I hereby acknowledge and observe this plugging.

DATE MAY 12 1986

INV. NO. 13790

Signed Jack Lacey  
(TECHNICIAN) S.D.RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1986  
CONSERVATION DIVISION  
Wichita, Kansas