

1 060792

340 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,809-00-00

NW NW NE , SEC. 25 , T 28 S, R 14 (W/E)

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name McGuire Well # A-1

Operator: TXO Production Corp.  
Name & Address 155 N. Market, Suite 1000  
Wichita, KS 67202

County Pratt 148.69

Well Total Depth 4575 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 406

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:45 pm Day: 29 Month: January Year: 19 86

Plugging proposal received from Jerry Pritchard

(company name) TXO (phone) 316-886-5606

were: 2 7/8" at 4529' PBTD 4529' Perfs at 4338-52'

1st plug sand back to 4285' and dump 1 1/2 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cem-nt, 10 sx gel, 1 sack hulls, and 170 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 pm Day: 29 Month: January Year: 19 86

ACTUAL PLUGGING REPORT Shot off at 918' and tubing went down hole.

1st plug sanded back to 4285' and dumped 1 1/2 sx cement on top of sand through bailer,

2nd plug pumped through swedge with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1

sack hulls, and 170 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 200 psi

FFR 4 1986 3-4-86 CONSERVATION DIVISION Wichita, Kansas

Remarks: No Recovery. Used 50/50 Pozmix 2% gel 3% cc by Halliburton. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

FEB 6 1986

Signed Paul A. Luthi (TECHNICIAN)

DATE

INV. NO. 12421