

1070067

TC:

API NUMBER 15-151-22,161-00-00

4-21

STATE CORPORATION COMMISSION

E/2 SW SW, SEC. 25, T 28 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 700 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1026 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LaDORA WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT

OPERATOR LICENSE # 32115

WELL TOTAL DEPTH 4640 150.80 FEET

OPERATOR: GIB EXPLORATION, INC

PRODUCTION CSG: SIZE _____ FEET _____

NAME AND 200 N. Harvey, Suite 800

SURFACE CASING: SIZE 10 3/4" FEET 320'

ADDRESS Oklahoma City, OK 73102

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Duke Drilling LICENSE NUMBER 5929

ADDRESS 310 W Central, Ste. 202 Wichita, KS 67202-1004

COMPANY TO PLUG AT: HOUR: 15:00p.m. DAY 21 MONTH: 4 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Joe Livingston

(COMPANY NAME) Duke Drilling, Inc. (PHONE) (316) 267-1331

WERE: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4600' with 50 sx cement, 2nd plug at 750' with 50 sx cement

3rd plug at 350' with 75 sx cement, 4th plug at 0-40' with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

PLUGGING PROPOSAL RECEIVED BY Scott Alberg

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 18:45p.m. Day: 21 MONTH: 4 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug at 4600' with 50 sx cement

2nd plug at 750' with 50 sx cement, 3rd plug at 350' with 75 sx cement

4th plug at 0-40' with 10sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

7th plug to circulate water well with 10 sx cement

4-23-98
RECEIVED
AMAS CORP COM
MAY 23 11:51

REMARKS: Used 60/40 Pozmix 6% Gel, by Allied, Ticket # 5859

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (BY NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

INVOICED
DATE MAY 04 1998
INV. NO. 50432