

1040989

8-18

API NUMBER 15- 151-21,434 -00-00

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION App. SE NE SE, SEC. 1, T 28 S, R 15 W/2
130 S. Market, Room 2078
Wichita, KS 67202

1745 feet from S section line

585 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5501

Lease Name Cosby Well # 1

Operator: Raymond M. Goodin Trust

County Pratt 156.00

Name & Address 3300 Carlock

Well Total Depth 4800 feet

Wichita, KS 67204

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address: P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 11 a.m. Day: 18 Month: 8 Year: 19 95

Plugging proposal received from Alan Vratle

(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 4783' w/300 sx cement, Perfs at 4486-4506'

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 18 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement. Maximum pressure 300 psi and shut in 100 psi.

4 1/2" collar welded in top of surface pipe.

RECEIVED STATE CORPORATION COMMISSION AUG 23 1995 8-23-95

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE SEP 01 1995

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 43398