

4-13-88

99R

To: 1061094
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-11,458-00-00

NW SE NE, SEC. 1, T 28 S, R 15 W/E

3680 feet from S section line

1140 feet from E section line

Lease Name Cosby Well # 2

County Pratt 152.43

Well Total Depth 4690 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 424

TECHNICIAN'S PLUGGING REPORT

Operator License # 3597

Operator: Servco Production/was Robert Gay
Name & Energy

Address P.O. Box 266
Plains, KS 67869

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 13 Month: 4 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4690' Perfs at 4476-4500'

1st plug sand back to 4425' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper plug and pump 180 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 13 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4425' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 650 psi and shut in 250 psi. 6% gel

Remarks: Used 60/40 Pozmix by Halliburton APR 14 1988
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas
Signed Paul A. Luthie (TECHNICIAN)

DATE 4-26-88

INV. NO. 20469