

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Texas Energies, Inc.

Complete Address 306 Bank of the Southwest Bldg., Amarillo, Tex. 79109

Lease Name Woolfolk Well No. 1

Location C NE SE Sec. 15 Twp. 28 Rge. 14 (E) X (W) X

County Pratt Total Depth 4280

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling.

Address 620 S. Lincoln, Liberal, Ks. 67901 License No. 511

Operation Completed: Hour 4 Pm. Day 29 Month 5 Year 1979

The above well was plugged as follows:

422' 8 5/8" casing w/350 sax cement. 4 1/2" casing set at 4278' w/250
sax cement. Plug back to 4233'-Preforated at 3969'-Sargent mixed &
pumped 35 sax cement in 4 1/2" casing-Release plug-Mixed & pumped
20 sax gel in casing. Pumped plug to 3380'- Pull 2633' 4 1/2" casing.
Set 40 sax cement plug at 313'-Set bridge at 40' & 12 sax cement to
top of casing.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 1 1979

6-1-79
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 6-1-79
INV. NO. 9751-W