

R

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JAN 8 1976
1-8-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Nesco Inc
Complete Address Box 379 Liberal, KS
Lease Name Lambert Well No. 1
Location C NE/NW/SW Sec. 14 Twp. 28 Rge. 14 (E) (WN)
County Pratt Total Depth 4150
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Sargent Casing Pulling
Address 620 S Lincoln Liberal, KS License No. 511
Operation Completed: Hour 4:00 PM Day 5 Month 1 Year 1976

The above well was plugged as follows:

354 ft 8 5/8 surface cement circulated. 4150 ft 5 1/2 long string
cemented with 150 sacks. Cast iron plug set at 3980 ft. Top perf.
3938 ft. Pump 20 sacks cement to 3850 ft. Pulled 2600 ft 5 1/2.
Pump 2 sacks hulls, 10 sacks gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]

Well Plugging Supervisor

DATE 1-8-76NO. 2533-W