

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-057-20,201-0000
authority June 30, 1981.

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720 Fourth Financial Center - Wichita, Kansas

Lease Name Christopher Well No. 1-22

Location C-5W Sec. 22 Twp 29S Rge. 21W (East) (West)

County Ford Total Depth 5307

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Production pipe set & tested but not produced

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas License No. 683

RECEIVED
STATE CORPORATION COMMISSION

Operation Completed: Hour: 10:20 AM Day: 9 Month: September Year: 1981

SEP 17 1981

Plugging Operations attended by Agent? All Part None

CONSERVATION DIVISION
Wichita, Kansas

The above well was plugged as follows:

There were 610' of 8 1/2" surface casing cemented circulated with 400 sks of cement. The Cheyenne was behind the surface casing. The 5 1/2" production pipe was set at 5307' with with 225 sks of cement plug back was at 5192' with perforations 5180' to 5184'. The 5 1/2" was squeezed and 1st plug set on bottom with 1 sks of hulls + 50 sks of cement. 2nd plug was set on top of 10 sks of gell + 2 sks of hulls pushed rubber plug to 575' put 50 sks of cement on top of rubber plug, 3rd plug set with 7 sks of gell + 2 sks of hulls + 35 sks of cement at 350'. 4th plug set at 40' to 0' with 8 sks of gell + 1 sks of hulls and 15 sks of cement.

I hereby certify that the above well was plugged as herein stated.
Plugging accomplished by Sun Oil well Cementing, Great Bend, Kansas

4010' of 5 1/2" in pipe reworked. INVOICED Signed: Paul Luthie
Conservation Division Agent

DATE 10/6/81
7811-W