

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Knoelling Well No. 1

Location C SW NW Sec. 6 Twp. 29 Rge. 21 (E) (W)

County Ford Total Depth 5365'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 7:30PM Day 23 Month 7 Year 1966

The Above well was plugged as follows:

8 5/8" to 277' circulated w/ cement. 5 1/2" to 5248' cemented.

Top Perforations 5168' Plug bottom w/ sand & 5 sacks cement.

Top of cement 5100' Mud 5100' to 600'

Spotted 30 sacks cement 600' to 500' Mud 500' to 325'

Spotted 30 sacks cement 325' to 225' Mud 225' to 35'

Plug. Hulls & 12 sacks cement 35' to 0. Company Pump.

Pulled 3198' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar L. Eves
Well Plugging Supervisor

DATE 7/26/66

INV. NO. 3635-W