

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 6 1967  
 9-6-67  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Intent to Drill,  
 filed August 23, 1967.

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil has this  
 date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Inc.

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: First Methodist Church Well No. # 1

Location: NW SW Sec. 28 Twp. 28 Rge. 12 (E)(W) W

County Pratt Total Depth 3782' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

402' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent