



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Voth of Time Petro. co. has this
date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company

Complete Address: 815 Union Nat'l. Bldg., Wichita 2, Kansas

Lease Name: Jay-Bolinger Well No. 1

Location: G NW NE Sec. 7 Twp. 29 Rge. 21 (E) (W)

County Ford Total Depth 5290' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Voth was instructed to plug the well as follows:

8 5/8" to 461' circulated w/ cement. 5 1/2" to 5289' cemented

Top Perforations 5037' Plug bottom w/ sand & 5 sacks cement. to 4950'

Mud 4950' to 400' Spot 35 sacks cement 400' to 300'

Mud 300' to 45' Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edmund Eves
Conservation Division Agent