

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

JUL 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Wasinger of Time Petroleum Co. has this

date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Co.

Complete Address: 815 Union National . . Wichita, Kansas

Lease Name: Jay-Bolinger Well No. # 2

Location: C W/2 NE Sec. 7 Twp. 29 Rge. 21 (W)

County Ford Total Depth 5111' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Wasinger was instructed to plug the well as follows:

8 5/8"-272' Circulated w/cement. 4 1/2"-5109' Cemented.


Plug bottome w/50 Sax.cement. Mud 4940' to 700'

Spotted 25 Sax.cement 700' to 625'. Mud 625' to 300'

Spotted 25 Sax.cement 300' to 225' Mud 225' to 45'

Plug, 15 Sax.cement 45' to 0

Very truly yours,

  
Conservation Division Agent