

15-057-30000-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1966

7-26-66

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gates of Time Petro. co. has this
date requested permission to plug the following described well:

Mr. Gates guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company.

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name: Knoelling Well No. 1

Location: C SW NW, Sec. 6 Twp. 29 Rge. 21 (W)

County Ford Total Depth 5365' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gates was instructed to plug the well as follows:

8 5/8" to 277' circulated w/ cement. 5 1/2" to 5248' cemented.

Top perforations 5168' Plug bottom w/ sand & 5 sacks cement.

Top of cement 5100' Mud 5100' to 600'

Spotted 30 sacks cement 600' to 500' Mud 500' to 325'

Spotted 30 sacks cement 325' to 225' Mud 225' to 35'

Plug, Halls & 12 sacks cement 35' to 0.

Very truly yours,

Edwards J. Jones
Conservation Division Agent