

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Bowman of Tomilson & Kathol has this date requested permission to plug the following described well:

Mr. Bowman guarantees payment of the plugging fee.

Operator's full Name: Crescent Oil & Gas Corporation

Complete Address: Box 412, Tulsa, Oklahoma

Lease Name: Heimuller Well No. # 1

Location: NE SW Sec. 9 Twp. 28 Rge. 14 (E) (W) W

County Pratt Total Depth 4760 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Bowman was instructed to plug the well as follows:

360' of 10 3/4" surface pipe, cement circulated with 275  
sacks. Fill hole with mud to 240', 1st cementing plug,  
1/4 sack hulls, cement with 25 sacks. Fill hole with mud to  
40', 2nd cementing plug, 1/4 sack hulls, cement with 15 sacks  
to base cellar. Bridge and cement rat hole with 2 sacks.

INVOICED  
DATE 6/24/63  
INV. NO. 7308-4

Very truly yours,

Archie Elving  
Conservation Division Agent