

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

Rec'd
6-2-65

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kans.

Lease Name: Woolfolk "A" Well No. # 1

Location: C NW SW Sec. 25 Twp. 28 Rge. 14 (E) (W) W

County Pratt Total Depth 4530' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

270' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 270', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent