

GP

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1965
4-20-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas

Lease Name Schenck Well No. # 1

Location SW NE NE Sec. 36 Twp. 28 Rge. 14 (E) (W)W

County Pratt Total Depth 4635'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Lauck Drilling Company, Inc.

Address: 301 S. Broadway, Wichita, Kansas License No. _____

Operation Completed: Hour 6:15PM Day 19th Month April Year 1965

The Above well was plugged as follows:

302' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged solid
with hulls on fluid at 275', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4-20-65

INV. NO. 10245-W