

*W* KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name C. Koenig Well No. 4

Location NW SE Sec. 28 Twp. 29 Rge. 34 (EX) (W)

County Haskell Total Depth 5501'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargent's Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 12 Month 7 Year 1966

The Above well was plugged as follows:

8 5/8" to 1827' circulated w/ cement. 5 1/2" to 5493' cemented.

Top Perforations 5243' Plug bottom w/ 20 sacks cement.

Top of cement 5050' Mud 5050' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Company Pump. Pulled 1980' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar E. Eves  
Well Plugging Supervisor

DATE 7/14/66

INV. NO. 3565-W