

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 - 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Fincham "D" Well No. # 1

Location C SE SE NW Sec. 1 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4760'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 11:15PM Day 30th Month July Year 1965

The Above well was plugged as follows:

961' of 8 5/8" surface pipe, cement circulated with 500 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 300', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with 2
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/2/65
INV. NO. 1568-W

Signed: Archie Elving
Well Plugging Supervisor