

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Eason Oil Company
Complete Address: Box 18755, Oklahoma City, Oklahoma
Lease Name Scott Well No. # 1
Location C SE NW Sec. 14 Twp. 29 Rge. 16 (E) (W) W
County Kiowa Total Depth 4780'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling Company
Address: Box 364, Great Bend, Kansas License No. 399
Operation Completed: Hour 4:30 PM Day 30th Month Oct. Year 1965

The Above well was plugged as follows:

250' of 13 3/8" surface pipe, cement circulated with 400 sacks. 2400' of
8 5/8" surface pipe, cemented with 125 sacks. 700' of 8 5/8" surface pipe
recovered from the hole. Fluid was up in the hole. Bridge plug was pushed
in fluid to 240', rock bridge from 240' to 230'. 3 sacks of cement and 2
sacks of Cal-Seal was mixed in barrel, and put on plug at 230', through
the dump bailer, and let set for 4 hours. Hole was bailed dry, and 47
sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 30 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/1/65
INV. NO. 2075-W