

Y KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company
Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas
Lease Name Sayre Well No. # 1
Location C NW NE Sec. 5 Twp. 29 Rge. 20 (E) (W) W
County Kiowa Total Depth 5265'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Company
Address: Box 405, Chase, Kansas License No. 436
Operation Completed: Hour 11:45AM Day 8th Month Feb. Year 1966

The Above well was plugged as follows:

352' of 8 5/8" surface pipe, cemented with 225 sacks. 5265' of 4 1/2" long
string, cemented with 150 sacks. Top perferation 5078'. Bottom of the
hole was sanded to 5060', and cemented with 3 sacks, through the dump
bailer. 3628' of 4 1/2" long string was recovered from the hole. Fluid in
the hole was at 310', bridge plug and rock bridge from 310' to 300',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/9/66
INV. NO. 2706-W

NOTICE

Correction on Legal Description.

Archie Elving

Archie Elving