

KANSAS

*JP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill;  
filed June 30, 1967.

Operator's Full Name Beardmore Drilling Company

Complete Address 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Wagner Unit Well No. # 1

Location SW SW Sec. 35 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5108'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Bldg., Wichita, Kansas 67202 License No.     

Operation Completed: Hour 11:00 A.M. Day 19th Month July Year 1967

The above well was plugged as follows:

445' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 180'. 1st cementing plug and 1/4 sack of hulls  
was pushed in fluid to 360', and cemented with 25 sacks, through the  
drill pipe, at 360'. Hole was filled with mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at  
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged  
and cemented with 2 sacks.

I hereby certify that ~~the~~ <sup>above</sup> well was plugged as herein stated.

INVOICED

DATE 7/20/67 JUL 20 1967

INV. NO. 5993-44 CONSERVATION DIVISION  
Wichita, Kansas

Signed: Archie Elving  
Well Plugging Supervisor