

K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Champlin Oil and Refining Co.

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Georgia Eubank Well No. # 1

Location C NW NE Sec. 28 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5205

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen and Smith

Address: P. O. Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 5: PM Day 4th Month Feb. Year 1963

The Above well was plugged as follows:

5193' of 4 1/2" long string cemented with 50 sacks. Plugged back to 5150'.
Top of perferation 5135'. Sanded to 5125' cemented with 3 sacks. 665'
of 8 5/8" surface pipe cemented with 300 sacks. Hole was filled with
mud to 200'. 10' rock bridge cemented with 20 sacks. Hole was filled
to 40' with mud. 10' rock bridge cemented with 10sacks to base cellar.
4960' of 4 1/2" pipe recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-8-63

INV. NO. 6549-W

Signed: Arlene Elving
Well Plugging Supervisor