

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name A. B. Sidener Well No. # 1

Location NW SE NE Sec. 17 Twp. 29 Rge. 19 (E) (W)W

County Kiowa Total Depth 5170'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:30PM Day 13th Month March Year 1966

The Above well was plugged as follows:

629' of 8 5/8" surface pipe, cemented with 500 sacks. 5169' of 5 1/2" long
string, cemented with 150 sacks. Plug back TD 5135'. Top perferation 5097'.
Bottom of hole was sanded to 5075, and cemented with 5 sacks, through the
dump bailer. 3200' of 5 1/2" long string was recoered from the hole. Hole
was filled with mud to 300', rock bridge from 300' to 290', and cemented
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/17/66
INV. NO. 2601-W

Signed: Audrie Elving
Well Plugging Supervisor