

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1966
12-27-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name White Shield Oil & Gas Corporation

Complete Address: 902 First National Bldg., Tulsa, Oklahoma

Lease Name Larkin Well No. # 1

Location NW NW SE Sec. 13 Twp. 29 Rge. 19 (E) (W)W

County Kiowa Total Depth 5242'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:00AM Day 23rd Month Dec. Year 1966

The Above well was plugged as follows:

661' of 8 5/8" surface pipe, cement circulated. 5237' of 5 1/2" long string,
cemented with 200 sacks. Plug back T.D. 5212'. Top perferation 5190'.
Bottom of the hole was sanded to 5175', and cemented with 5 sacks, through
the dump bailer. 2888' of 5 1/2" long string was recovered from the hole.
Fluid level in the hole was at 400'. Bridge plug was pushed in fluid to
660', bridge plug and rock bridge from 660' to 650'. 10 sacks of cement
was mixed in a barrel, and put on plug at 650', through the dump bailer.
This hole is to be left open for a fresh water well.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE: 12/27/66

INV. NO: 4519-62