

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks 67202

Lease Name Graves Gas Unit Well No. 1

Location C NE/SW/NE Sec. 9 Twp 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5006

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:00PM Day 16 Month 4 Year 1970

The above well was plugged as follows:

249 ft of 8 5/8 surface pipe cemented with 225 sacks. 5006 ft of

5 1/2 long string cemented with 100 sacks. Plug back to 4975 ft. Top

perf. 4910 ft. Sand back to 4900 ft, 5 sacks cement with bailer.

Pulled 2837 ft of 5 1/2. Pumped 15 sacks of gel., & 100 sacks cement

to surface. Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bibeister  
Well Plugging Supervisor

INVOICED

DATE 4/20/70

INV. NO. 1750-W