

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1981
APL CONSERVATION DIVISION
Wichita, Kansas

12-8-81

15-097 20,792

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Nelson Enterprise

Complete Address 1675 Broadway Suite 2770 Denver Colo. 80202

Lease Name Dargal Well No. 1

Location C-NE-SE Sec. 9 Twp. 29 SRge. 18 (East)(West)

County Kiowa Total Depth 5047

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed & tested but not produced

Plugging Contractor Sargant's casing pulling service

Address 620 S. Lincoln Box 506 Liberal Kansas 67901 License No. 571

Operation Completed: Hour: 4:00 PM Day: 2 Month: December Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 450' of 8 3/8" surface casing cement circulated. There is 5047' of 4 1/2" production pipe cemented to 4200'. They plugged back to 4900'. The perforations are from 4510' to 4516'. 1st plug pumped 1 lbs hulls + 20 lbs of cement to bottom. 2nd plug on solid bridge at 1200' with 35 lbs of cement. 3rd plug on solid bridge at 460' with 35 lbs of cement. 4th plug 40' to 0' on solid bridge with 10 lbs of cement. Plugging accomplished by Sargant's casing pulling service. The cement used was common cement. Reamed 3416' of 4 1/2" production pipe.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: Paul Luther
Conservation Division Agent

DATE 1-7-82

INV. NO. 8993