

To: 1 020278  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-28  
15-129-10554-0000 233 R  
API NUMBER 15- Drill Completion Date 7/17/56

C NW SE, SEC. 27, T 34 S, R 42 WEX  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Riley Well # 4-27  
County Morton 150.28  
Well Total Depth 4624 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1498

Abandoned Oil Well  Gas Well  Input Well  SHD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 26 Month: 12 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 4624' PBTD 4582' Perfs at 4564-76' DV'd at 3400' TOC 2610'

1st plug set cement retainer at 4540', pump mud in hole, spot 25 sx cement on top of  
retainer with tubing, 2nd plug pump 30 sx cement at 2400',  
3rd plug run 50 sx cement at 1598-1398', 4th plug spot 35 sx cement at 700',  
5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 p.m. Day: 28 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 4540', pumped mud in hole, spotted  
25 sx cement on top of retainer with tubing,  
2nd plug pumped 30 sx cement at 2400',  
3rd plug ran 50 sx cement at 1598-1398',  
4th plug spotted 35 sx cement at 700',  
5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2421' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-12-90

INV. NO. 26995

STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
JAN 4 1990  
1-4-90

CONSERVATION DIVISION  
Wichita, Kansas

Signed Glenn R. Barlow (TECHNICIAN)