

TO: 1052229

2-24

API NUMBER 15- 151-21530 -00-01

STATE CORPORATION COMMISSION

C NW SW , SEC. 6 , T 28 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION

1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4620 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME Schoonover WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT

OPERATOR LICENSE # 31953

WELL TOTAL DEPTH 4749 FEET

OPERATOR: Case Production Company

PRODUCTION CSG: SIZE 4 1/2 FEET 4716

NAME AND 110 Gwendola

SURFACE CASING: SIZE 8 5/8" FEET 429

ADDRESS McKinney TX 75070

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL # D-24,699 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Mikes Testing & Salvage Inc. LICENSE NUMBER 31529

ADDRESS P.O. Box 467 Chase, KS 67524

COMPANY TO PLUG AT: HOUR: 2:00 pm DAY: 24 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Mike Kelso

(COMPANY NAME) Mikes Testing & Salvage Inc. (PHONE) 316-938-2943

WERE: SAND BOTTOM OF WELL TO 4400' AND PLACE 4 SX OF CEMENT ON TOP OF SAND WITH A DUMP BAILER . TO PULL PIPE AND PUMP DOWN THE SURFACE PIPE WITH:

300# OF COTTEN SEED HULLS-10 SACKS OF GEL-50 SACKS OF CEMENT-10 SACKS OF GEL- 100# OF HULLS - 8 5/8" WIPER PLUG - 100 SACKS OF CEMENT. CEMENT BLEND WILL BE 60/40 POZMIX 6% GEL

 PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:37 PM DAY: 24 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 4400' AND PLACED 4 SX OF CEMENT ON TOP OF IT WITH A DUMP BAILER, PUMPED DOWN THE WITH: 300# OF COTTEN SEED HULLS- 10 SACKS OF CEMENT-10 SACKS OF GEL-100# OF COTTEN SEED HULLS-RELEASED A 8 5/8" WIPER PLUG- 100 SACKS OF CEMENT. MAXIMUM PUMP PRESSURE 600 PSIG. SUSTAINED SHUT IN PRESSURE 200 PSIG

REMARKS: USED 60/40 POZMIX 6% GEL CEMENT BY ALLIED CEMENTING RECOVERED 2300' OF 4 1/2" PIPE (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-213

DATE 3-10-98

INV. NO. 50184