

To: 1 051530
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-13

API NUMBER 15-151-21,903-00-00

94 R

C SW NW, SEC. 20, T. 28 S, R. 14 W/E

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30752

Lease Name Sillin Well # 1

Operator: Pipe Recovery Inc.

County Pratt 154.63

Name & Address P.O. Box 7

Well Total Depth 4758 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 2 Year: 19 92

Plugging proposal received from Rick Davis

(company name) Pipe Recovery Inc. (phone) 316-793-3922

were: 4 1/2" at 4749' w/100 sx cement, Perfs at 4162-70'

1st plug sand back to 4110' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 13 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4110' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2200
(If additional description is necessary, use BACK of Wichita, Kansas.)

I (client) ~~will~~ observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 2-27-92

INV. NO. 34661