

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22337-00-01
Spot: NWSESESE Sec/Twnshp/Rge: 35-25S-4E
580 feet from S Section Line, 480 feet from E Section Line
Lease Name: RICE PARMALEE Well #: 5
County: BUTLER Total Vertical Depth: 2475 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2474		0 SX
SURF	8.625	204		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2015 9:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES AND REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2015 2:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) SANDED BACK PERFS AND TAGGED W/ TUBING AT 2390. 2) PUMPED 15 SKS OF 60/40 4% CEMENT W/3% CACL. 3.) PULLED TUBING OUT OF HOLE, RAN IN HOLE W/WIRELINE AND TAGGED CEMENT AT 2350'. 4.) PERFORATED CASING W/ 4 SHOTS AT 263'. 5). RAN IN 8 JOINTS OF TUBING TO APPROX. 260' AND PUMPED 106 SKS OF 60/40 4% CEMENT W/ 0.5% CACL, CIRCUALTED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2442	2447		CSG

KCC WICHITA
JUN 02 2015
RECEIVED

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OILFIELD SERVICE, EL DORADO, KS. TICKET #48322.

Plugged through: TBG

6/10/15 CKM

District: 02

Signed Jonathan Hill
(TECHNICIAN)

JK