

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-21349-00-01
Spot: SWSE Sec/Twnshp/Rge: 9-31S-40W
668 feet from S Section Line, 1916 feet from E Section Line
Lease Name: CONLON Well #: 1-9H
County: MORTON Total Vertical Depth: 5690 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2400		WITH 15 SX CMT
CIBP		3750		
CIBP		4125		
PC		3000		WITH 575 SX CMT
PROD 4.5		5689	0	WITH 225 SX CMT
SURF 8.625		1868		WITH 790 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/12/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 2400' WITH 2 SX CMT. FILL 4 1/2" WITH WATER. RUN CBL TO DETERMINE TOC. RUN TBG AND/OR PERFORATE AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2015 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2400' WITH 15 SX CMT THROUGH TBG. TEST CASING TO 600#. HOLDING. RUN CBL FROM 2400' TO 50'. NO CEMENT BEHIND THE 4 1/2" CASING. PERFORATE 4 HOLES AT 1900'. RUN TBG TO 1500'. TAKE INJECTION RATE INTO PERFS @ 1 1/2 BPM @ 500#. PUMP 25 SX CMT FOLLOWED BY 50# HULLS & 25 SX CMT TO PERFS LEAVING 1/2 THE CMT INSIDE THE CASING & 1/2 THE CMT OUTSIDE THE CASING. USED BRADEN HEAD SQUEEZE METHOD. FULL CIRCULATION. PERFORATE 4 HOLES AT 550'. CIRCULATE CMT TO SURFACE WITH 170 SX CMT, LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5260	5315		
4020	4026		
2792	2798		
2434	2798		

KCC WICHITA
JUN 01 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED
MAY 22 2015
KCC DODGE CITY

Signed

Ken Jehlik
SA

(TECHNICIAN)

6/10/15 CKM