

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26764-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 26-14S-19W
680 feet from N Section Line, 1665 feet from W Section Line
Lease Name: SUNLEY-CURTAIN Well #: 1-26
County: ELLIS Total Vertical Depth: 3836 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3834	2515	145 SX
SURF	8.625	221		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2015 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO INC. Phone: (785) 621-2610

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 200 # hulls and 16 sx gel.
Perforations: 3746' - 3752' Arb
PBSD- 3809'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2015 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

05/13/2015- Pumped 50 sx cement w/200 # hulls mixed in. Displaced with 8 sx of gel.
Pressure got to high to pump all 16 sx gel.
05/15/2015- 9am. Tagged cement at 3615'. Cut casing at 2515'. Pulled casing to 2000' and pumped 125 sx cement w/200 # hulls mixed in. Pulled casing to 1400' and pumped 40 sx cement. Pulled casing to 625' and pumped 130 sx cement to circulate cement to surface. Pulled the rest of the casing. Hole standing full.

GPS: 38.81097 -099.40522
680' FNL 1665' FWL
NE SW NE NW

Perfs:

Top	Bot	Thru	Comments
3748	3752		
3746	3752		
3741	3744		

KCC WICHITA
MAY 28 2015
RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

CM

6/10/15CKM

MAY 15 2015