

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22032-00-00
Spot: NWNE Sec/Twnshp/Rge: 7-32S-10W
4777 feet from S Section Line, 1987 feet from E Section Line
Lease Name: MCKEEVER Well #: 2-7
County: BARBER Total Vertical Depth: 3755 feet

Operator License No.: 33936
Op Name: GRIFFIN, CHARLES N.
Address: PO BOX 347
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3500		WITH 2 SX CMT
PROD	5.5	3711	2012	WITH 100 SX CMT
SURF	8.625	224		WITH 215 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2015 8:45 AM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: JR GRIFFIN Company: CHARLES GRIFFIN Phone: (972) 342-4648

Proposed Plugging Method: SET CIBP @ 3500' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 275' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2015 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3500' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3613	3619		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

6/10/15 CKM

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAY 19 2015
KCC DODGE CITY

KCC WICHITA,
JUN 03 2015
RECEIVED