

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JOHN C. WOELK Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1966

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of E. K. Edmiston Drlg., Co has this
 date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Woods Petroleum-Kenneth Rupp

Complete Address: 1035 Wichita Plaza, Wichita, Kansas

Lease Name: Nichols Well No. # 1

Location: C SW NE Sec. 35 Twp. 29 Rge. 18 (E)(W) W

County Kiowa Total Depth 5004' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

400' of 8 5/8" surface pipe, cement circulated with 180 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Cliving
 Conservation Division Agent