

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bowen of Amoco has this

date requested permission to plug the following described well:

Mr. Bowen guarantees payment of the plugging fee.

Operator's full Name: Amoco Production Co.

Complete Address: Box 432, Liberal, Kansas

Lease Name: Rohmeyer Operating Well No. 1

Location: App C NE NW Sec. 30 Twp. 29 Rge. 32 ~~(E)~~ (W)

County: Haskell Total Depth 5800' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Bowen was instructed to plug the well as follows:

8 5/8" to 796' circulated w/ cement. 5 1/2" to 5514' cemented.

Top perforations 5302' Plug bottom w/ Bridge plug & 5 sacks cement.

<u>Top of cement 4560'</u>	<u>Mud 4560' to 2600'</u>
<u>Spot 30 sacks cement 2600' to 2500'</u>	<u>Mud 2500' to 1200'</u>
<u>Spot 30 sacks cement 1200' to 1100'</u>	<u>Mud 1100' to 850'</u>
<u>Spot 40 sacks cement 850' to 750'</u>	<u>Mud 750' to 40'</u>
<u>Plug, Mulls & 10 sacks cement 40' to 0'.</u>	

Very truly yours,

Conservation Division Agent