

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Robert White of Robert F. White has this

date requested permission to plug the following described well:

Mr. Robert White guarantees payment of the plugging fee.

Operator's full Name: Robert F. White

Complete Address: 714 Union Center Wichita, Kansas

Lease Name: Collingwood Well No. # 1

Location: C NW NE Sec. 8 Twp. 29 Rge. 34 (E) (W)

County Haskell Total Depth 5649' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Robert White was instructed to plug the well as follows:

8 5/8" 1800' Circulated w/cement. 5 1/2" 5649' Cemented.


Perforations 5445' to 4578'

Sand 5649' to 4500' 5 Sax.cement 4500' to 4450'

Mud 4450' to 710' 10' Rock Bridge 710' to 700'

35 Sax.cement 700' to 600' Mud 600' to 50'

Rock Bridge 50' to 40' 15 Sax.cement 40' to surface.

Very truly yours,

 Conservation Division Agent