

15-081-10204-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1973

CONSERVATION DIVISION
Wichita, Kansas

9-21-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ross of Ashland has this

date requested permission to plug the following described well:

Mr. Ross guarantees payment of the plugging fee.

Operator's full Name: Ashland Exploration Co.

Complete Address: Box 127, Satanta, Kansas 67870

Lease Name: L.E. Hickman Well No. 1

Location: SE SW Sec. 16 Twp. 29 Rge. 34 ~~XX~~ (E) (W)

County: Haskell Total Depth 5515' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Ross was instructed to plug the well as follows:

8 5/8" to 1850' circulated w/ cement. 5 1/2" to 4076' cemented.

Top perforations 4073' Plug bottom w/ 25 sacks cement.

Top of cement. 3800' Mud 3800' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls ^{cc} 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent