

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ipson of Ashland Oil & Refining Co has this date requested permission to plug the following described well:

Mr. Ipson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: L.E. Hickman Well No. 2

Location: NW SE Sec. 16 Twp. 29 Rge. 34 (E) (W)

County Haskell Total Depth 5496' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ipson was instructed to plug the well as follows:

8 5/8" to 1818' circulated w/ cement. 5 1/2" to 5496' cemented.

Top perforations 5342' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Lues
Conservation Division Agent