

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 7 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones, Inc. has this

date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.Operator's full Name: Hinks Petroleum Co., c/o Gabbert-Jones Inc.Complete Address: 514 Orpheum Bldg., Wichita, KansasLease Name: Thomas Well No. # 1Location: C SW SE Sec. 22 Twp. 30 Rge. 7 (E) (W) WCounty Kingman Total Depth 4327' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Gabbert was instructed to plug the well as follows:202' of 8 5/8" surface pipe, cement circulated. Fill holewith drilling mud to 200', 1st cementing plug, bridge withhulls, and cement with 25 sacks. Fill hole with drillingmud to 40', 2nd cementing plug, bridge with hulls, and cem-ent with 10 sacks to base cellar. Bridge and cement rat holewith 2 sacks.

Very truly yours,

Archie Elving