

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Garvey Drilling Co. has this
date requested permission to plug the following described well:Mr. Pfannenstiel guarantees payment of the plugging fee.Operator's full Name: Petroleum Inc.Complete Address: 352 N. Broadway, Wichita, KansasLease Name: Wells "I" Well No. # 1Location: SW SE NE Sec. 20 Twp. 30 Rge. 7 (E) (W) WCounty Kingman Total Depth 4320 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Pfannenstiel was instructed to plug the well as follows:

255' of 8 5/8" surface pipe, cemented with 200 sacks. Fill
hole with drilling mud to 270', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Conservation Division Agent