


WELL PLUGGING RECORD

All Information Completely  
Required Affidavit  
or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 2 Twp. 28S Rge. 9W (X) (W)



Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner Time Petroleum Company  
Lease Name Hay Well No. #1  
Office Address 815 Union National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-4-63 19  
Application for plugging filed 10-4-63 19  
Application for plugging approved 10-4-63 19  
Plugging commenced 10-4-63 19  
Plugging completed 10-4-63 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4015 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	258.68'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud to 250' 1st Plug 1/4 sack hulls & 25 sacks cement.

Heavy Mud to 40' top plug 1/4 sack hulls & 10 sacks cement. cement to bottom of cellar. 2 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 9 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1963

My commission expires April 1, 1967 Ulanda Nichols Notary Public

DRILLER'S LOG

COMPANY: Time Petroleum Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: HAY #1  
 LOCATION: C NE SE Sec. 2-28S-9W  
 KINGMAN COUNTY, KANSAS  
 COMMENCED: 9-25-63  
 COMPLETED: 10-4-63

0	68	Surface Soil & Sand
68	80	Sand
80	695	Redbed
695	1194	Shale
1194	1206	Anhydrite
1206	1250	Shale & Lime
1250	1810	Lime
1810	2895	Lime & Shale
2895	3025	Lime
3025	3216	Lime & Shale
3216	3255	Sand & Shale
3255	3360	Sand
3360	3405	Shale & Lime
3405	4011	Lime
4011	4015	Mississippi Chat
	<u>4015</u>	<u>Rotary Total Depth - D. &amp; A.</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION

OCT 9 1963

CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used Surface Casing @ 258.68' with landing joint Cemented with 200 sacks Quickset Cement.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hay #1, located C NE SE of Section 2, Township 28 South, Range 9 West, Kingman County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 8th day of October, 1963.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967