


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 26 Twp. 28S Rge. 7 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C NW/4 SW/4  
Lease Owner Hall-Jones Oil Corporation & Walters Drilling Co.  
Lease Name Rosenkranz Well No. 1  
Office Address 510 Orpheum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 24th, 1961 19  
Application for plugging filed December 24th, 1961 19  
Application for plugging approved December 24th, 1961 19  
Plugging commenced December 24th, 1961 19  
Plugging completed December 24th, 1961 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation Mississippian Depth to top Bottom Total Depth of Well 4400 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug with Hulls and 20 Sacks Cement, mudded to 40' plug and Hulls and 10 sacks Cement. Plugged rat hole.

JAN 3 1962

1-3-1962

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) Robert F. Walters  
ROBERT F. WALTERS, Partner  
510 Orpheum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 19 61

R. L. Abel  
R. L. Abel Notary Public.

My commission expires January 4th, 1964



15-095-01339-0000

ROSENKRANZ #1

LOCATION:	C NW/4 SW/4 Section 26-28S-7W Kingman County, Kansas	DATE SPURRED: 12-9-61
OPERATOR:	WALTERS DRILLING CO. & HALL-JONES OIL CORPORATION	ROTARY COMPLETION: 12-24-61
CONTRACTOR:	Walters Drilling Co.	ELEVATION: 1583 GL 1585 DF 1588 KB
SURFACE CASING:	8-5/8" set @ 260' w/190 sacks cement	
OIL STRING:	None	

L O G


(Figures indicate bottom of formation)

Clay & Soil	0-20'
Sand	60'
Shale & Shells	1095'
Lime & Shale	1500'
Lime	1710'
Lime & Shale	1875'
Lime	2020'
Lime & Shale	3140'
Shale & Sand	3246'
Lime	3620'
Lime & Shale	3670'
Lime	3712'
Lime & Shale	4001'
Lime	4023'
Lime & Chert	4117'
Lime	4270'
Shale	4310'
Shale & Sand	4370'
Lime	4375'
Sand	4400'
Total Depth	4400'

JAN 3 1962

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By   
ROBERT F. WALTERS, Partner

Subscribed and sworn to before me  
this 27th day of December, 1961

  
Notary Public R. L. Abel

My commission expires January 4th, 1964