


WELL PLUGGING RECORD 15-095-60434-0001



KINGMAN County. Sec. 21 Twp. 28S Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner GABBERT-JONES, INC.
Lease Name LOWE Well No. 1 W/D
Office Address 830 SUTTON PLACE, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 24, 19 68
Application for plugging filed (PHONE 6/24/68) JUNE 27, 19 68
Application for plugging approved JUNE 24, 19 68
Plugging commenced JUNE 24, 19 68
Plugging completed JUNE 25, 19 68
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RALPH WARREN
Producing formation Depth to top Bottom Total Depth of Well 4385 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	250	8-5/8"	250'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 235 FEET. SET FIRST PLUG @ 235 FEET WITH 1/2 SACK HULLS AND 25 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG @ 40 FEET WITH 1/2 SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE @ 1:00 AM, JUNE 25, 1968.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

830 SUTTON PLACE, WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of JUNE 19 68



FEBRUARY 1, 1972.

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

15.095-60434-0001

LOWE #1 WASHDOWN & DEEPEN
C NE SW SECTION 21-28S-7W
KINGMAN COUNTY, KANSAS

OLD INFORMATION:

WAS ARTHUR OIL #1 LOWE, SPUD 7/18/58 WITH 250' 8-5/8" CASING, CEMENTED W/175 SACKS,
D & A 7/30/58, T.D. 3992'.

NEW INFORMATION:

COMMENCED: JUNE 19, 1968
COMPLETED: JUNE 25, 1968

OPERATOR - GABBERT-JONES, INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	250	CEMENT AND MUD	DRILL AND WASH
250	3992	MUD	WASH DOWN
3992	4140	LIME	
4140	4170	LIME AND CHERT	
4170	4206	LIME	
4206	4243	CHERTY LIME	
4243	4290	CHERTY LIME AND SHALE	
4290	4379	SHALE	
4379	4385	SIMPSON	
4385	TD		DRY AND ABANDONED.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1968
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL
WASHED DOWN AND DEEPENED IN THE C NE SW SECTION 21-28S-7W, KINGMAN COUNTY, KANSAS, TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE,
ON THIS 27TH DAY OF JUNE, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO
BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED
TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND
PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND
YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1972.

