


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 21 Twp. 28S Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Artnell Company & Leben Drilling, Inc.
Lease Name Lowe Well No. 1
Office Address 533 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 29 1958
Application for plugging filed July 29 1958
Application for plugging approved July 29 1958
Plugging commenced July 29 1958
Plugging completed July 29 1958
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3992' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 200' with 20 sacks of cement, 1/2 sack of hulls through drill pipe, plug at 35' with one-half sacks of hulls and 10 sacks of cement. Job completed at 10:00 P. M. on July 29, 1958.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim B. McWilliams (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
Jim B. McWilliams
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 31th day of July, 1958

My commission expires December 14, 1961

Elaine H. Taylor
Elaine H. Taylor Notary Public.

PLUGGING
FILE SEC 21 T 28 R 7W
BOOK PAGE 120 LINE 18

RECEIVED
AUG 4 1958
STATE CORPORATION COMMISSION
Wichita, Kansas

D R I L L E R S L O G

15-095-60434-0000

#1 Lowe

CASING RECORD: 215' of used 8-5/8" surface casing.	COMPANY: Artnell Company & Leben Drilling, Inc.	DESCRIPTION: C NE ^{SW} Section 21-28S-7W Kingman County, Kans.
TOTAL DEPTH: 3992'	COMMENCED: July 17, 1958 COMPLETED: July 29, 1958	ELEVATION: 1547' KB


D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	10	Ran 215' (11 Jts.) of used 8-5/8" surface casing; cemented with 175 sacks of cement, 2% Gel and 2% Calcium Chloride.
Sand	10	25	
Red Shale	25	110	
Gray Shale	110	190	
Shale	190	215	
Shale & Shells	215	1215	
Shale & Lime	1215	2892	
Lime & Shale & Sandy Lime	2892	3040	
Lime & Shale	3040	3225	
Lime	3225	3470	
Lime & Shale	3470	3580	
Lime	3580	3665	
Lime & Shale	3665	3727	
Lime	3727	3763	
Lime & Shale	3763	3895	
Lime & Shale & Chert	3895	3966	
Lime & Shale	3966	3980	
Lime	3980	3992	
TOTAL DEPTH 3992'			DST #1 Packer set @ 3970'. Total Depth 3980'; tool open 1 hour, gas to surface in 3 min. Gaged 771,000 cu. ft. Recovered 150' muddy water. IFP 210 lbs. FFP 210 lbs. BHP 1450 lbs. in 20 minutes.
			DST #2 Packer set @ 3982'. Total Depth 3992'; tool open 1 hour, gas to surface in 7 min. gaged 240,000 cu. ft. declined to 139,000 cu. ft. Recovered 240' salt water. IFP 130 lbs. FFP 130 lbs. BHP 1340 lbs. in 20 minutes.

STATE OF KANSAS)
) ss:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


Jim B. McWilliams, Secy-Tres.

Subscribed and sworn to before me this 31th day of July, 1958.

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1958


Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1961

CONSERVATION DIVISION
Wichita, Kansas

PLU...ING
FILE SEC 21 28 7W
BOOK PAGE 120 LI 18