

15-095-20614-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 17 Twp. 28 Rge. 7 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NE

Lease Owner Mack Oil Co.
Lease Name Reynolds #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5/23/79 _____ 19____
Plugging completed 5/25/79 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	none
				4 1/2"	4469	Y&R 3229'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4000' and set 4 sacks cement. Loaded hole, shot pipe at 3248', pulled 76 joints. Set rock bridge at 471' and ran 8 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this _____)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 79

My commission expires _____



Margaret Melcher
Notary Public.

DRILLER'S LOG

15-095-20614-0000

COMPANY: Mack Oil Co.

SEC. 17 T. 28S R. 7W

WELL NAME: Reynolds #1

LOC. SE NW NE

COUNTY: Kingman

RIG NO. #7

TOTAL DEPTH 4470'

ELEVATION

COMMENCED: 8-3-77

COMPLETED: 8-14-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 215' w/200 sx. common, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4183' w/25 sx. poz., 10% salt, 3/4 of 1% CFR2, and 125 sx. common, 18% salt, 3/4 of 1% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Sand, Shale & Redbed	270
Redbed & Shale	1115
Shale	1550
Shale & Lime	2060
Shale	2190
Shale & Lime	3455
Lime & Shale	3790
Lime	3980
Shale & Lime	4087
Lime	4470
<u>ROTARY TOTAL DEPTH</u>	<u>4470</u>

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1979

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)
COUNTY OF Sedgwick) SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the
Reynolds #1 well.

Wilson Rains

Wilson Rains

Subscribed and sworn to before me this 15 day of August, 1977.

My Appointment Expires:

10-4-79

Juanita M. Green

Juanita M. Green

