

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1990
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 5-097-20,912-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kennedy & Mitchell, Inc. OPERATORS LICENSE NO. 6462 *de/91*

ADDRESS P. O. Box 1045 Woodward, Oklahoma 73802 PHONE # (405) 254-3032

LEASE (FARM) Dalke WELL NO. 50-692 WELL LOCATION SE NW SW COUNTY Kiowa

SEC. 31 TWP. 29S RGE. 18W (E) or (W) TOTAL DEPTH 5110' PLUG BACK TD 5079'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 550' CEMENTED WITH 350 SACKS

CASING SIZE 4 1/2" SET AT 5109' CEMENTED WITH 250 SACKS

PERFORATED AT 5052'-5062'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 20 sack cement plug to perforations.

Set 50 sack cement plug at 1220', 50 sack cement plug at 580' and 10 sack cement plug at 40'.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes
(If not, explain) Sent in when ACO-1 was filed

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

H. D. Hollingsworth PHONE # (405) 254-3032

ADDRESS P. O. Box 1045 Woodward, Oklahoma 73802

PLUGGING CONTRACTOR Sargent's Casing Pulling LICENSE NO. 269 *6547 de/91*

ADDRESS P. O. Box 506 Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: *H. D. Hollingsworth*
(Operator or Agent)

DATE: July 12, 1990

Q



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 13, 1990

Kennedy & Mitchell, Inc.
P.O. Box 1045
Woodward, OK 73802

Dalke #50-692
SE NW SW 31-29-18W
Kiowa County, KS
API No. 15-097-20,912

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801