

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation CommissionP. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Kiowa County, Sec. 21 Twp. 29 Rge. (E) 18 (W)
Location as "NE/CNWSW" or footage from lines C NE SE
Lease Owner Misco Industries, Inc.
Lease Name Fay Thorn Well No. 4
Office Address Misco Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed June 7 19 74
Application for plugging approved June 10 19 74
Plugging commenced June 28 19 74
Plugging completed Aug. 22 19 74
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5827 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			375'	8 5/8"	375'	none
			5568'	7"	5568'	2995.87

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4100' and dumped 6 sacks of cement.

Set 10' rock bridge at 240' and plugged well with 4 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of August, 19 74

My commission expires July 16, 1978

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kan.

15-097-10078-0001


COPY

Company GULF OIL CORP.
Farm Fay Thorn No. 4

SEC. 21 T. 29 R. 18 W
C NE SE

Total Depth. 5000'
Comm. 10-31-56 Comp. 11-20-56
Shot or Treated.
Contractor.
Issued. 12-15-56

County Kiowa KANSAS



CASING:
8 5/8" 375'

Elevation. 2232' DF

Production. Dry

Figures indicate Bottom of Formations.

shale-red bed	756
red bed-shells	1504
red bed-shale-shells	1865
red bed-shells	2327
shale-lime	2465
lime	2547
lime-shale	2759
lime	2839
shale-lime	3288
shale	3736
shale-shells	3773
shale-lime	3986
lime	4153
shale	4300
lime	4309
lime-shale	4405
lime	4808
shale-lime	4849
lime	4914
lime-chert	4970
lime	5000
Total Depth	

TOPS:	
Heebner	4128
Douglas	4160
Brown lime	4302
Lansing-Kansas City	4312
Mississippian chert	4923
Mississippian lime	4970

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1974
CONSERVATION DIVISION
Wichita, Kansas