

State

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH R 23W

Ford County. Sec. 19 Twp. 29S Rge. 23 (E) (W) W

Location as "NE/CNWxSWx" or footage from lines NW SW
Lease Owner Tenneco Oil Co.
Lease Name E. M. Birney Well No. 1
Office Address Box 163, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed 2-19-62 19
T Application for plugging filed 2-19-62 19
29 Application for plugging approved 2-19-62 19
S Plugging commenced 2-19-62 19
Plugging completed 2-19-62 19
Reason for abandonment of well or producing formation P&A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top - Bottom - Total Depth of Well 5361 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	341	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 335 feet with 1/3 sack hulls and 20 sacks of cement.
Set second plug at 35 feet with 1/3 sack hulls and ten sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1962

CONSERVATION DIVISION
Wichita Kansas
2-23-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Co., Inc.
Address 514 Orpheum Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Blair E. Amour
Box 163, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of February, 19 62

My commission expires Oct. 13, 1962. John D. Liman Notary Public.



GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

ELMA MARGARET BIRNEY #1
C NW SW SECTION 19-29S-23W
FORD COUNTY, KANSAS

COMMENCED: FEBRUARY 2, 1962
COMPLETED: FEBRUARY 19, 1962

OPERATOR - TENNECO OIL COMPANY.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	355	SAND & SHALE	RAN 373' OF 8-5/8" CASING, SET @ 354' W/250 SACKS CEMENT.
355	620	RED BED	
620	635	ANHYDRITE	
635	815	SHALE	
815	2140	SHALE & SHELLS	
2140	2610	LIME & SHALE	
2610	3000	LIME	
3000	3215	LIME & SHALE	
3215	3595	LIME	
3595	3718	LIME & CHALK	
3718	4380	LIME	
4380	4499	LIME & SHALE	
4499	4902	LIME	
4902	4940	SHALE & LIME	
4940	5361	LIME	
5361	TD		DRY & ABANDONED

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1962
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NW SW SECTION 19-29S-23W, FORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 20TH DAY OF FEBRUARY, 1962, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963

Vera A. McKenzie

VERA A. MCKENZIE, NOTARY PUBLIC