


15-081-10009-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Haskell County. Sec. 13 Twp. 29 Rge. 32W (E) (W)
Location as "NE/CNW/SE" or footage from lines SE SE SE
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Boatright Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5/8 19 54
Application for plugging filed 7/15 19 55
Application for plugging approved 7/18 19 55
Plugging commenced 7/17 19 55
Plugging completed 7/22 19 55
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 5435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	565 1/2'	None
				5"	4566'	2214'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 4470', dumped 5 sacks cement at 4470' with dump bailer. Top of cement, 4445'. Filled hole with mud to 560', set 10' rock bridge, dumped 20 sacks cement. Top of cement, 490'. Filled with mud to 35', set rock bridge, dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 55

My commission expires 6/17/58

Notary Public. RECEIVED STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 13 T 29 R 32W
BOOK PAGE 134 LINE 38

JUL 29 1955 7-29-1955
CONSERVATION DIVISION
Wichita, Kansas

Bennett & Roberts Drilling Co.
Boatright #1

SE SE SE Sec. 13-29-32
Haskell County, Kansas

R.T.D. 5435

Tops:

Comm: 4-5-54
Comp:

Heebner	4154	(-1263)
Lansing K.C.	4283	(-1392)
Marmaton	4757	(-1866)
Cherokee	4929	(-2038)
Morrow	5187	(-2296)
Mississippian (Chester)	5230	(-2339)
Ste. Genevieve	5417	(-2556)

Casing
10 3/4 @ 565 w/400 sx. cmt.
5 @ 4566 w/175 sx. cmt.

Formations	Depth:
Surface Clay & Sand	320
Sand & Shale	525
Blue Shale	566
Blue Shale	640
Sand	900
Red Bed	1030
Sand	1120
Sand & Shale	1660
Shale Sand & Shells	1812
Shale & Gyp Nnhy.	1930
Shale & Anhy.	2380
Anhy. & Shale	2655
Anhy. & Lime	2700
Lime & Shale	2740
Lime	2785
Lime & Shale	2895
Lime	2947
Lime & Shale	3037
Sandy Lime & Shale	3087
Lime & Shale	3154
Lime	3185
Lime & Shale	3587
Lime	3768
Lime & Shale	3865
Lime	3938
Lime & Chalk	3978
Lime	4097
Lime & Chalk	4119
Lime & Shale	4172
Lime	4212
Lime & Shale	4239
Lime	4472
Lime Shale Chert	4478
Lime	4944
Lime & Shale	4955
Lime	5177
Lime & Shale	5220
Lime & Sandy Shale	5240
Lime & Shale	5289
Lime	5338
Lime & Shale	5435

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1954
CONFIDENTIAL

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

Louisa Bond

Subscribed and sworn to before me this 12th day of May, 1954.

Wesley Hummel
Notary Public

My commission expires 6/17/54

PLUGGING
FILE SEC 13 T 29 R 21W
BOOK PAGE 134 LINE 38